

# Big Picture..Strawperson

- Cavity fabrication
- Existing infrastructure in USA
- Strawman plan for SMTF modules
  
- Industrialization of cavity fabrication
  - Warren Funk

# Review Goals/Strategies of SMTF

- Advance US regional SRF capability in anticipation of strong needs for ILC, RIA, Proton Driver, Light Sources...
- Gain experience to prepare us to develop a large-scale production plan, or to integrate with the evolving ILC production plan
- Use existing SRF infrastructure in many labs as much as possible (see next few slides)
- Integrate with DESY capabilities as much as possible.
- Integrate US industries from the start to develop US industrial capability for upcoming projects
- US industry personnel to use lab infra-structure (to save up-front investment cost)
- Work towards specific projects, e.g one ILC rf unit, by 2008, one cw rf module by 2007...
- Adopt a phased approach...there has to be lots of learning!

# Existing Infrastructure Slides

## Few Examples From

- Jlab
- Cornell
- LANL
- MSU
- Fermilab
- Argonne
- SLAC (e-beam welder)
- AES (industrial)
  - Meyer Tool
  - Sciacky

JLAB  
Cavity  
Vertical  
Test  
Areas




# Jlab - Cryomodule Assembly and Test Areas



Cryomodule Test Facility (CMTF)

# SRF Infrastructure

## Deep Drawing




## 1000 Sq Ft Clean Room



## Ebeam Welding



## Chemical Etching



## High Pressure Rinsing





Cornell  
Cavity  
Test Pits

# Los Alamos Nat Lab - SRF Facilities

2. Assembly with flanges, couplers, valves, etc. in a 2600 ft<sup>2</sup> Clean room



1. Ultra-pure water is used for HPR and assembly.



140 ft.



3. Set on the cryostat inser



100 ft.







4. Inserted in a 38" cryostat with radiation shield



High-pressure rinsed in a clean room.

Control, tuning  1943-2003





**SLAC**

# S/C FIVE (5) CELL CAVITY-700MHz RRR250

---



**Advanced Energy  
Systems, Inc.**


In US

*Putting Accelerator Technology to Work*


APT, LANL

Fermilab, 3.9 GHz

BNL 700 MHz



# Plan View of BCP Lab Area at AES (13ft wide X 16ft long - inside)



# Goals for CW SRF



- Common R&D interests across many CW SRF proposals are:
- Demonstrate 20 MV/m CW operations at Q values  $> 3 \times 10^{10}$ .
- Operate at 20 MV/m at a  $Q_{\text{ext}} > 1 \times 10^7$  for low beam loading applications.
- Address the following major issues for CW operation and high current:
  - Thermal management
  - HOM damping
  - Cavity tuning control
  - Power coupler designs

# Several RF Structures Under Development Already to Address Similar Issues

- At different frequencies and with different parameters
- Cornell is conducting a study towards 7-cell, 1300 MHz cavities with beam pipe HOM couplers good for 100 mA beam current, and for frequencies up to 40 GHz
- A high-current ERL prototype is under construction at BNL. The objective is to demonstrate 0.5 ampere CW current at about 20 MeV. (R&D towards electron cooling of RHICA)
- Jlab upgrade module (Renaissance)


# Cornell

7-cell, large beam pipe,  
1.3 GHz



HOM  
couplers  
inside  
cryomodule  
200 watts

# A Complete ERL for R&D




## Prototype


# Jlab- Renaissance

- Cavity designs for application to CEBAF 12 GeV Upgrade
- Design operating temperature: 2.09 K at cavities
  - 250 W dynamic loss per cryomodule
  - 31 W per cavity
  - 44 W per active meter
  - 460  $\mu$ A CW beam


# LL Cavities for Renascence - VTA Performance



1500 MHz, 7-cells, Low-Loss Shape



# LL Cavity System




Tuner

DESY - Coax HOM  
couplers

WG input  
coupler 15  
kW

# Renascence Cryomodule



## Example SMTF Scenario: 20 MV/m, for the CW unit for high current, high Q and high $Q_{ext}$

- Design “common denominator module” for CW operation
- Identify subassemblies to be prototyped, e.g cavity/coupler assembly
- Build Prototype subassemblies with industrial collaboration (see ILC example for more)
- Test prototype subassemblies at lab
- Consider design/process optimizations before launching production for all components of one full module
- Build one module following scenario similar to ILC module (with industry)
- Test at SMTF
- Beam test at SMTF

# Example ILC-Related goal

- Adopt a phased approach toward performance goals
- Start with existing design/process
- Adopt all techniques necessary to aim towards 35 MV/m,  $Q = 10^{10}$
- Build first module in “learning mode” with industrial collaboration
- Determine “learning-mode” performance..(OK to be < 35 MV/m)
- Identify areas where improvements are needed
- Install design/process optimizations before launching next 3 modules
- Build 4 + modules
- Test modules at SMTF
- Beam test modules at SMTF

# Strawman Plan for Cavity/He Vessel/Cavity String...

- Planning/Definition
  - Form co-ordinating group (ILC involvement)
  - Define first “module from DESY” based on discussions with DESY, others (TTF-like)
  - Obtain first SMTF module from DESY (provide help)
  - Obtain designs from DESY, obtain procedures from DESY
  - Get up to speed on processing...(e.g process 9-cell cavities)
- Plan first US SMTF module = same as first DESY SMTF module (TTF-like)

# Strawman Plan for Cavity/He Vessel/Cavity String...

- Make cavity parts, clean cavity parts
- Weld cavity
- Field flatness tuning
- Heat treatment (“800” C or 1400 C as determined best)
  - Could also be done at half-cell stage, proven to reach 35 MV/m in single cells at Cornell
- Electropolishing, high pressure rinse
- Vertical acceptance test
- Weld He vessel, re-measure field flatness
- High pressure rinse
- Attach input coupler, tuner...(see later slides)
- Individual cavity/coupler/tuner assembly tests at high power (like CHECHIA)
- Cavity/coupler assembly ready for string assembly
  
- Measurements and Quality control for all steps above

# Cavity Fabrication Facilities Locations

- Parts fabrication, eg deep drawing
  - AES, Meyer Tool...
  - (Jlab, Cornell, LANL, FNAL, if needed)
- Parts chemistry
  - AES..
  - Jlab, Cornell, LANL, FNAL...
- Sub-assembly e-beam welding
  - Sciacky...
  - Jlab, Cornell, SLAC, LANL
- Final Welding
- Heat treatment
  - Cornell, Jlab
- Chemical etching
  - Jlab, Cornell, Argonne/FNAL..
- Electropolishing
  - Jlab
- HPR
  - Jlab, Cornell, LANL, MSU, FNAL
- Tuning
  - Jlab, Cornell, LANL
- Vertical Test
  - Jlab, Cornell, LANL
- Weld helium vessel
- Check field profile
- HPR
- Send to string assembly location
- ....

# Input Coupler Scenario

- Order input couplers from CPI or AMAC...
- Set up high power coupler test facility with RF power
  - Possible locations: Jlab, LANL, Fermilab
- Assemble/bake high power couplers
- High power test
- Send to cavity string assembly location

# Tuner Scenario

- Select tuner design
- Carry out further engineering necessary
- Order tuner parts
- Assemble tuners at cavity assembly test facility

# Cavity String Preparation

- Receive cavity/He vessel/input coupler/tuner
- Assemble and test (like-CHECHIA)
- Send to string assembly location
  
- Receive other vacuum and alignment parts
- Set up and align clean room string support structure
- Assemble cavity string
- Align cavity string
- Fix bellows
- Leak test
- SC quads (chose the design, get specs)
- Infrastructure needed assuming SMTF location:
  - Large clean room with string support structure
  - high pressure rinsing

## Time Estimate for Experienced People From Fermilab Engineering Study

### AT DESY

The preparation labor for each cavity is about 185 man-hours prior to assembly into a string. This includes chemistry, tuning, and oven bake out.

Multiplying by 8 cavities, this gives 185 man-days per cryomodule for this cavity prep work.

The assembly of the TTF cavity string takes about 15 man-days. The assembly of the string into the module takes approximately 60-80 man-days (see below).

This totals ~270 man-days ~1.1 man-year.

**SMTF first module will take much longer, of course**